

Waste Transfer Station Upgrade

**Client**

Ceredigion  
County Council

**Location**

Aberystwyth  
Ceredigion

**Date**

2012



The works involved the removal of two existing retaining walls and installation of larger reinforced concrete retaining walls to increase capacity within the transfer station. A new reinforced concrete floor was also installed to improve the drainage within the building.

- Excavation and breaking of existing concrete walls and removal to tip off site.
- Installation of new reinforced concrete foundations.
- Installation of formwork and false work for 2no 3m high retaining walls.
- Excavation and disposal of existing concrete floor.
- Re-grading sub-base to increase falls within the floor and the installation of a new reinforced concrete floor.
- Installation of a new drainage channel within the pit.

